



CONSTRUCTION PHASE HEALTH & SAFETY PLAN

JOB 1: THE PADDOCKS

***Client:
Michael Thomas***

***CDM Coordinator:
David Smith, Smith Architects***

***Principal Contractor:
Tony Wilson, MJ Moorlands Builders & Contractors***

***Site Address:
The Paddocks, Green Lane, Long Village, Bristol, Avon, BS30 1DE***

CONTENTS

1	DESCRIPTION OF PROJECT	3
1.1	PROJECT DESCRIPTION	3
1.2	KEY DATES	3
1.3	EXISTING STRUCTURES	3
1.4	GROUND CONDITIONS	3
1.5	EXISTING TRAFFIC SYSTEMS	3
1.6	WORKING RESTRICTIONS	3
2	MANAGEMENT OF THE WORK	4
2.1	MANAGEMENT STRUCTURE	4
2.2	HEALTH & SAFETY GOALS	5
2.3	MONITORING & REVIEWING	6
2.4	LIAISONS BETWEEN PARTIES ON SITE	6
2.5	CONSULTATION WITH THE WORKFORCE	6
2.6	THE EXCHANGE OF DESIGN INFORMATION	6
2.7	HANDLING DESIGN CHANGES DURING THE PROJECT	7
2.8	SELECTION & CONTROL OF CONTRACTORS	7
2.9	THE EXCHANGE OF HEALTH & SAFETY INFORMATION BETWEEN CONTRACTORS	7
2.10	SITE SECURITY	7
2.11	SITE INDUCTION	7
2.12	ON-SITE TRAINING	7
2.13	WELFARE FACILITIES	7
2.14	THE REPORTING & INVESTIGATION OF ACCIDENTS & INCIDENTS INCLUDING NEAR MISSES	8
2.15	FIRST AID	8
2.16	SITE RULES	8
2.17	FIRE & EMERGENCY PROCEDURE	8
3	CONTACTS	9
4	ARRANGEMENTS FOR CONTROLLING SIGNIFICANT SAFETY RISKS	12
4.1	DELIVERY & REMOVAL OF MATERIALS & EQUIPMENT	12
4.2	DEALING WITH SERVICES	12
4.3	ADJACENT LAND USE	12
4.4	STABILITY OF STRUCTURES WHILST CARRYING OUT CONSTRUCTION WORK, INCLUDING TEMPORARY STRUCTURES & EXISTING UNSTABLE STRUCTURES	12
4.5	PREVENTING FALLS	12
4.6	WORKING WITH OR NEAR FRAGILE MATERIALS	12
4.7	CONTROL OF LIFTING OPERATIONS	12
4.8	MAINTENANCE OF PLANT & EQUIPMENT	12
4.9	WORKING ON EXCAVATIONS & POOR GROUND CONDITIONS	12
4.10	WORK ON OR NEAR WATER WHERE THERE IS A RISK OF DROWNING	13
4.11	TRAFFIC ROUTES & SEGREGATION OF VEHICLES & PEDESTRIANS	13
4.12	STORAGE OF MATERIALS & WORK EQUIPMENT	13
4.13	ANY OTHER SIGNIFICANT SAFETY RISKS	13
5	ARRANGEMENTS FOR CONTROLLING SIGNIFICANT HEALTH RISKS	14
5.1	THE REMOVAL OF ASBESTOS	14
5.2	DEALING WITH CONTAMINATED LAND	14
5.3	MANUAL HANDLING	14
5.4	USE OF HAZARDOUS SUBSTANCES, PARTICULARLY WHERE THERE IS A NEED FOR HEALTH MONITORING	14
5.5	REDUCING NOISE & VIBRATION	14
5.6	ANY OTHER SIGNIFICANT HEALTH RISKS	14
6	THE HEALTH & SAFETY FILE	15
6.1	LAYOUT & FORMAT	15
6.2	ARRANGEMENTS FOR THE COLLECTION AND GATHERING OF INFORMATION	15
6.3	STORAGE OF INFORMATION	15

1 DESCRIPTION OF PROJECT

1.1 PROJECT DESCRIPTION

5 Unit New Build Housing Development.

Housing development including demolition of existing structures on site.

1.2 KEY DATES

Start Date: 22/02/07

Duration: 52 weeks

Anticipated Completion Date: 22/02/08

Phase 1 Start Date: 22/02/07

Phase 2 Start Date: 01/04/07

Phase 3 Start Date: 18/10/07

1.3 EXISTING STRUCTURES

Barn complex with party walls.

1.4 GROUND CONDITIONS

Existing footings and slab from existing barn structure. Clay and running sand.

1.5 EXISTING TRAFFIC SYSTEMS

Main roadway with traffic calming measures (speed bumps).

1.6 WORKING RESTRICTIONS

Residential 8pm - 5pm and no weeknds. Adjacent to school - school restrictions.